



Project#2024 Town of Holyrood Culvert Replacement



Please be advised that the division of Municipal Infrastructure of the Department of Transportation and Infrastructure have updated the Municipal Water, Sewer and Roads Master Construction Specifications, and will continue to the enforcement of strict adherence to these specifications.

The specification is currently available online at:

<https://www.gov.nl.ca/ti/mi/mwsr/#spec>

“These project documents have been prepared for use with and require being read in conjunction with the “Municipal Water, Sewer and Roads Construction Specifications” latest revision, as published by the Department of Municipal Affairs Province of Newfoundland and Labrador.

34 Salmonier Line
Holyrood, NL, Canada
A0A 2R0

p. +1-709-229-7252
Robert Stacey

Robert.Stacey@Holyrood.ca
www.holyrood.ca

INDEX

Town of Holyrood

Project #2024 Town of Holyrood Culvert Replacement

	<u>Page</u>
Title Page	(1)
Index	(2)
Instruction to Bidders	(3)
List of documents and description of work	(4-6)
Specifications & Addenda	(6)
Tender Form	(7)

COR CERTIFICATION

to Be Produced before the Award

Proof of Insurance

To be Produced before the Award

The NLSCA administers the COR program to help ensure OHS standardization for the province's construction companies. Until recently there have been three categories within the NLCSA's COR program. A company could have received a Letter of Good Standing stating *In Process*, *Audit Pending*, or *Certificate of Recognition*.

Tenders for contracts that would typically have a COR requirement must use the following language:

The Contractor shall within 14 days of award of the contract, and prior to commencement of the work, provide a Letter of Good Standing stating Certificate of Recognition (COR) certified from the Newfoundland and Labrador Construction Safety Association (NLCSA)."

Instruction to Bidders

Town of Holyrood

Project #2024 Town of Holyrood Culvert Replacement

Project Team

Owner: Town of Holyrood
P.O. Box 100
Holyrood, NL
A0A 2R0

Consultant: Town of Holyrood

Date: May 10, 2024

Project Number: #2024 Town of Holyrood Culvert Replacement

Tender Closing Date: May 24, 2024, 4:00 pm

Work Completion Date: July 31, 2024

All work to be done in conjunction with “**Municipal Water, Sewer and Roads Construction Specifications**” latest revision, as published by the Department of Municipal Affairs Province of Newfoundland and Labrador.

Bids can be submitted to the Town Office at 34 Salmonier Line by 4:00 pm May 24, 2024

In an envelope clearly marked ATTN: Robert Stacey “Town of Holyrood Culvert Replacement 2024.

Town of Holyrood

Project #2024 Town of Holyrood Culvert Replacement

List of documents and description of work

1. List of Spreadsheet

n/a

2. Site of the works

The Site of the Works in the Town of Holyrood, NL

3. Description of the Works

The scope of work under this Tender includes Culvert Replacement in the Town of Holyrood.

All culverts must be free and clear of any obstruction once installation is complete.

All cut ends of culvert are the property of the Town.

Item 1: 158 Country Path The scope of work in this item includes the removal and disposal of one 24" x 30ft Galvanized culvert and replacing with one 24" x 30ft HDPE culvert supplied by the Town of Holyrood. Contractor is responsible to deliver the HDPE culvert to the work site and disposal of the existing culvert. Contractor to ensure that the existing overflow culvert at this location is not damaged during excavation. Any damage to this culvert will be the responsibility of the contractor.

Item 2: 165 Country Path: The scope of work in this tender document includes the removal and disposal of one 18" x 40ft Galvanized culvert and replacing with one 21" x 40' HDPE culvert supplied by the Town of Holyrood. Contractor is responsible to deliver the HDPE culvert to the work site and disposal of the existing culvert.

The culverts will require proper rip rap as per the specifications detailed in the Government of Newfoundland and Labrador, Department of Transportation and Works Highway Design Division Section 610 "RIP RAP TREATMENT".

Culverts must be installed at correct elevation and slope for maximum efficiency.

All Areas to be paved to be graded and shaped in preparation of paving and or class A or B and is included in the price of this project. This work will also include compaction to 95% or better proctor.

The Town of Holyrood will be responsible for contracting out the pavement portion of this project. Contractor is responsible for saw cutting the areas. Town will mark/identify the saw cuts for the contractor with paint.

Removed galvanized culvert must be broken down and deposited in the scrap metal bin at the municipal depot.

Lowest bid, or any may not be accepted.

The Town reserves the right to change the unite quantities in any area as the project may determine. The Town may spend less than the total contract dollar amount as to meet Town of Holyrood budget allotments.

Bidders may request a site meeting as detailed in the tender advertisement.

Specifications

Town of Holyrood

Project #2024 Town of Holyrood Culvert Replacement

“These project documents have been prepared for use with and require being read in conjunction with the “Municipal Water, Sewer and Roads Construction Specifications” latest revision, as published by the Department of Municipal Affairs Province of Newfoundland and Labrador.

Please be advised that the division of Municipal Infrastructure of the Department of Transportation and Infrastructure have updated the Municipal Water, Sewer and Roads Master Construction Specifications, and will continue to the enforcement of strict adherence to these specifications.

The specification is currently available online at:
<https://www.gov.nl.ca/ti/mi/mwsr/#spec>

All ditching must conform to The Town of Holyrood’s Engineering Design Guidelines for Subdivisions Section 7.5 Side Ditches.

7.5.1

Side ditches shall be constructed along both sides of streets that do not have piped storm drainage systems. In all cases the invert of the ditch shall be below sub grade of the street and shall conform to the following dimensions:

- Minimum Bottom Width =
- 1.0 m Minimum Depth =
- 1.0 m
- Maximum Side Slope = 2:1

List of Addenda

The following addenda, if and when issued, shall form part of the contract documents

Addendum No

NAME OF CONTRACTOR/TENDERER:

Print X _____ Signiture X _____

ADDRESS:

Total Tender Amount | **Total including HST for project # 2024 Culvert Replacement**
inclusive.