

## 2024 Kieley's Lane Infrastructure Upgrades



"These project documents have been prepared for use with and require being read in conjunction with the "Municipal Water, Sewer and Roads Construction Specifications" latest revision, as published by the Department of Municipal Affairs Province of Newfoundland and Labrador. This Publication is available on the department website under the following link:

http://www.ma.gov.nl.ca/ma/publications/index.html

#### INDEX

#### **Town of Holyrood**

#### Project #2024 Kieley's Lane Infrastructure Upgrades

|   | Page |
|---|------|
| Title Page                                | (1)  |
| Index                                     | (2)  |
| Instruction to Bidders                    | (3)  |
| List of documents and description of work | (4)  |
| Specifications & Addenda                  | (5)  |
| Bid form                                  | (6)  |

#### Attached document.

COR CERTIFICATION

see below

The NLSCA administers the COR program to help ensure OHS standardization for the province's construction companies. Until recently there have been three categories within the NLCSA's COR program. A company could have received a Letter of Good Standing stating *In Process, Audit Pending*, or *Certificate of Recognition*.

Tenders for contracts that would typically have a COR requirement must use the following language:

The Contractor shall within 14 days of award of the contract, and prior to commencement of the work, provide a Letter of Good Standing stating Certificate of Recognition (COR) certified from the Newfoundland and Labrador Construction Safety Association (NLCSA)."

MI will be updating front end documents accordingly, but in the meantime, funding recipients and their consultants should be aware of this change. In terms of the project award process, if a contractor cannot provide a *Letter of Good Standing stating Certificate of Recognition (COR) Certified* from the NLCSA within the timeframe specified within the Award letter then they are to be disqualified.

#### **Instruction to Bidders**

#### Town of Holyrood

Project #2024 Kieley's Lane Infrastructure Upgrades

Project Team

Owner:

Town of Holyrood

P.O. Box 100 Holyrood, NL A0A 2R0

Consultant:

Town of Holyrood

Date:

June 10, 2024

Project Number:

2024 Kieley's Lane Infrastructure Upgrades

RFQ Closing Date:

June 21, 2024

Work Completion Date:

August 31, 2024

All work to be done in conjunction with "Municipal Water, Sewer and Roads Construction Specifications" latest revision, as published by the Department of Municipal Affairs Province of Newfoundland and Labrador. This Publication is available on the department website under the following link: <a href="http://www.ma.gov.nl.ca/ma/publications/index.html">http://www.ma.gov.nl.ca/ma/publications/index.html</a>

All work to be done in conjunction with the requirements of the "Guidelines for the Design, Construction and Operations of Water and Sewerage Systems": http://www.env.gov.nl.ca/env/waterres/waste/groundwater/report.html

Quotes can be submitted to the Town Office at 34 Salmonier Line by Friday June 21, 2024,, 12:00 pm E.S.T.

In an envelope clearly marked ATTN: Robert Stacey "2024 Kieley's Lane Infrastructure Upgrades"

E-mails can be sent to info@holyrood.ca, only e-mails received before 12:00pm Friday June 21, 2024 will be accepted.

#### Town of Holyrood

#### Project #2024 Kieley's Lane Infrastructure Upgrades

#### List of documents and description of work

#### 1. Site of the works

The Site of the Works in the Town of Holyrood, NL

#### 2. Description of the Works

The scope of work under this Tender includes the installation of a new 2" continuous Municipex water line, and new 6" PVC sewer line approximately 80 meters in length through the Hickey's Funeral Home Parking lot to service the three residences at the bottom of Kieley's Lane, the funeral home and crematorium.

Contractor responsible for, and include price for the following:

- 1. Locate and excavate the end of the existing 6" ductile iron water main and 6" sewer line.
- 2. Installation of a new gate valve on the existing 6" ductile iron. Gate valve cover to be set at proper grade for paving. Town water main to be shut down during the 6" gate valve installation, this will need to be completed at a time early in the morning hours such as 4am, time to be agreed upon between the town and the contractor.
- 3. Reduce the line from the 6" gate valve to 2" using a 6" ductile iron stub with a 6" MJ end cap tapped NPT thread, and male adaptor to except the 2" Municipex with proper clamps and fittings.
- 4. Install new 2" Municipex using a 300ft roll through the parking lot, connecting the service lines to the funeral home and crematorium with new fittings, to the connection points of the three houses on Kieley's Lane. New curb stops for the crematorium and the funeral home to be set at proper grade for paving.
- 5. Install flush hydrant at the termination point of the 2".
- 6. Flush system through hydrant to ensure disinfection before residential hookup occurs.
- 7. Connect all three houses to the new water line with new clamps and fittings.
- 8. Install proper fitting on existing 6" sewer line to accept the new 6" PVC sewer line.
- Install new 6" sewer line through the parking lot, connecting the service lines from the funeral home and crematorium with new fittings, to the connection point of the three houses on Kieley's Lane
- 10. Excavation and removal of excavated materials.
- 11. Approved Back fill and bedding materials.
- 12. Provide water and sewer to the three residences on Kieley's Lane, the funeral home and crematorium until final connections are required.
- 13. Notify Residence on Kieley's Lane of water disruption.
- 14. Public Works to inspect all connections before back fill commences.
- 15. All permits and approvals from regulatory bodies.
- 16. Installation of an 18" x 120" HDPE culvert on site.
- 17. Insulation on sewer pipe where adequate coverage cannot be obtained.
- 18. Removal of existing infrastructure.
- 19. Contractor to determine best method(s) of trenching to satisfy current construction standards.

All Areas to be paved to be graded and shaped in preparation of paving.

Damages to existing infrastructure will be the responsibility of the contractor.

Bidders can request a site meeting as detailed in the RFO advertisement.

### **Specifications**

#### Town of Holyrood


Project #2024 Kieley's Lane Infrastructure

"These project documents have been prepared for use with and require being read in conjunction with the "Municipal Water, Sewer and Roads Construction Specifications" latest revision, as published by the Department of Municipal Affairs Province of Newfoundland and Labrador. This Publication is available on the department website under the following link:

> http://www.ma.gov.nl.ca/ma/publications/index.html List of Addenda

The following addenda, if and when issued, shall form part of the contract documents

Addendum No



# 2024 Kieley's Lane Infrastructure Upgrades

| NAME OF CONTRACTOR |              |    |  |
|--------------------|--------------|----|--|
| Print_X            | Signiture_X_ |    |  |
| ADDRESS:           |              |    |  |
| 4                  | 72           |    |  |
| Amount for project |              |    |  |
| \$                 | \$ HST       | 2. |  |
|                    |              |    |  |